



14 February 2011

New AZO Review



Construction Progress:

- Installation of terrazzo nears completion
- Installation of counters in the rental car spaces nears completion
- Permanent light fixture installation continues
- Installation of carpeting has begun
- Installation of passenger boarding bridges nears completion.

By the numbers

Red brick used in the construction of the terminal:



Exterior: 80,000 bricks
Interior: 84,000 bricks

Sustainability at AZO

In the design and construction of the new terminal, RS&H and Skanska have employed sustainable practices. The building features materials and sources were selected to balance both sustainable design and cost-efficient construction and maintenance. Examples include:

- Building materials from regional sources, which reduces the project's environmental impact by reducing pollution caused by transportation of material to the site;

Carpet installation in Rental Car areas nears completion.

- Carpets specifically engineered to handle heavy traffic in addition to being Green Label Plus Certified for indoor air quality;



- Ultrasonic and infrared dual technology occupancy sensors are used to turn off lights when spaces are not occupied. These sensors, used in offices and restrooms, help conserve energy;



Sensor in an office ceiling.

- Sheet metal used on the project contains about 23% post-consumer recycled content;

(continued on page 2)

Rumor has it...

This week's rumor:

The new terminal will have bamboo flooring and decorative indoor fountains.

The fact of the matter:

Neither bamboo flooring nor decorative fountains are being installed in the new terminal.

When the 2005 design of the terminal was under development, both bamboo and fountains were included; however, both items were removed from the design

currently under construction. Information on the flooring and artwork will be included in a future newsletter.

Hear a rumor? Contact Ann, athorvik@chrysalisglobal.com

Counters for Rental Car and Limousine services

The appearance of the rental car agency counters and the limousine rental counter will be consistent with airline ticketing counters and boarding gates.



On right, the yellow tape is used during the assembly and installation of the counters' faces. At left, agencies will customize their shelving behind counter.

Next Time

In the next newsletter:

- Construction Progress
- The "Plane Truth"
- Rumors



Installation of the countertop in the Business Center is complete. The Center will have seating and ample power outlets for charging devices.

Sustainability

- A combination of fluorescent, metal halide, and LED light fixtures were selected to provide illumination for spaces by providing a high level of energy efficiency at the intended light levels; and
- Carpets are part of the manufacturer's nationwide reclamation program. They will collect any and all used carpet, eliminating landfill use.



Some of the types of lighting used in the new terminal.



If power should fail, the terminal's new generator can support critical equipment, systems, and safety devices.

Contact Us

Do you have questions, comments, or rumors? Please contact Ann and she'll address them:

Ann Thorvik

Chrysalis Consulting, LLC

(317) 809-0110 cell

athorvik@chrysalisglobal.com

The "Blizzard of 2011"

The "Blizzard of 2011" came and went, and the Airfield Operations team worked 16-hour shifts to clear the 10" of snow and drifting snow, providing safe conditions for weather-delayed flights.



Snowblower "Sno-Go1" prepares the airfield for an incoming flight.

